

New in May 2026

Updates

- Heatpunk UK has been updated to enact various MCS changes to operating temperature and air change rates.
 - [Operating temps for post-2006 buildings have been increased in almost all rooms.](#)
 - [Air change rates now default to 0.5 for all rooms except internal.](#)
 - [Using the standard ventilation method now uses a fixed default air permeability of \$12 \text{ m}^3/\text{h.m}^2\$ @ 50 Pa rather than using an occupancy-based estimator as before.](#)
- Skip button added to consumption task menu.

Fixes

- Correction to post-2006 room temperatures when using specified air permeability.
- Fix to errors caused by deleting region corner with a height.
- Floor plan task can now handle materials that have u-value of 0.
- Sidebar displays correctly when opening material library from home page.
- Fix to floor plan PDF upload when there is more than one page.
- Emails no longer all show as sent based on one email.
- Property details for previously opened project no longer cached on new projects.

Revision #6

Created 7 May 2026 08:54:14 by Daisy

Updated 1 July 2026 08:00:24 by Daisy